

ATTENTION



ADDENDUM 1

BID OPENING: August 29, 2024


BID: EPOXY CHIP SEAL BRIDGE DECK PRESERVATION PROJECT IN YAVAPAI COUNTY, AZ PROJECT #2423754

- 1. CLARIFICATION:** Per project specification for Epoxy Chip Seal, the number of Epoxy or Epoxy Urethane layers and aggregate layers shall be per the manufacturer's recommendations. The overlay thickness shall be comprised of a minimum of two layers and the total application shall not be less than 7.5 gallons per 100 square feet. The first course shall have coverage not less than 2.5 gal/100 square feet. The second course shall have coverage not less than 5.0 gallons per 100 square feet. Item 2 description of the Bid Schedule has been revised, as attached, to read 'Epoxy Chip Seal Coat' instead of 'Single Epoxy Chip Seal' for clarity.
- 2. ADDITION:** ADOT Section 402-4 – Pavement Gridding. When approved by the Engineer, the Contractor may use diamond gridding to remove surface irregularities.
- 3. REVISION AND REPLACEMENT:** Special Provisions Item 4 – Notice to Proceed - The contract time is anticipated to begin on the notice to proceed date which shall be on September 30, 2024. All bidding contractors shall be full prepared to commence work on this notice to proceed date.
- 4. REVISION AND REPLACEMENT:** Bid Schedule. Bidding contractor must complete and submit "BID SCHEDULE – REVISED AUGUST 27, 2024" to bid this project. Revised engineer's estimate of the project is \$269,748.20.

This addendum cover sheet shall be signed and included in the bid package as acknowledgment of receipt of ADDENDUM 1.

Bidder's Signature and Title

Company Name



ADOT SECTION 402-4 – Pavement Grinding

Description:

The work under this section shall be in accordance with Section 402-4 of ADOT Standard Specifications and as modified herein.

The surface area receiving a grinding shall be specified by the Engineer in the field. No Profile Index measurements shall be required for this project.

Method of Measurement:

Measurement for work under this section shall be in accordance with Section 402-4.04 of the ADOT Standard Specifications.

Pavement grinding will be measured by the square feet of pavement ground and accepted. The quantity will be determined by multiplying the width by the length of the ground area.

Basis of Payment:

Payment for work under this section shall be in accordance with Section 402-4.05 of the ADOT Standard Specifications.

Pay Item:

Pavement Grinding

Pay Unit:

Square Feet (SF)