

BID SCHEDULE

OLD HIGHWAY 66 OVERLAY (FY 25-26) IN YAVAPAI COUNTY, ARIZONA

PROJECT #2450129

1. Yavapai County Engineering Department hereby requests the services of a licensed contractor for **OLD HIGHWAY 66 OVERLAY (FY 25-26) IN YAVAPAI COUNTY, ARIZONA - PROJECT #2450129**, in accordance with the attached plans and these specifications.
2. All bids shall be on this form and signed by the owner or his legally authorized and binding representative. The low bidder will be required to sign a legally binding contract to perform the requested work at the price quoted.
3. The Contractor shall provide all Quality Control Testing and certification for the project. Yavapai County shall provide Quality Assurance Testing and inspection for the project.
4. The unit prices submitted shall include all costs to produce the required finished product and shall also include but not be limited to fees, taxes, fines, permits, royalties, testing and quality control, oils, admixtures, insurance, bonding and any other costs incidental to this project.
5. A Bid Bond will be required in the amount of 10% of the total amount bid. A Performance Bond will be required in the amount of 100% of the total amount bid. A Payment Bond will be required in the amount of 100% of the total amount bid.

The successful bidder will be determined on the basis of the bid submitted for **OLD HIGHWAY 66 OVERLAY (FY 25-26) IN YAVAPAI COUNTY, ARIZONA - PROJECT #2450129**.

The following quantities are approximate. Payment will be based in field measured quantities.

The following bid shall be valid for a period of Sixty (60) days.

I, _____, representing _____ (Company Name), _____ (Address and Phone Number), _____ (Contractor's License Number), do hereby submit the following bid for **OLD HIGHWAY 66 OVERLAY (FY 25-26) IN YAVAPAI COUNTY, ARIZONA - PROJECT #2450129**.

Signed

Date

BID SCHEDULE

OLD HIGHWAY 66 OVERLAY (FY 25-26) IN YAVAPAI COUNTY, ARIZONA

PROJECT #2450129

No.	Description	Quantity	Unit	Unit Price	Total Amount Bid
1	2" OVERLAY ASPHALTIC CONCRETE PAVEMENT, 1/2" HIGH TRAFFIC, PG 64-22	11,202	TN		
2	BITUMINOUS TACK COAT (0.10 GAL/SY)	9,623	GAL		
3	PAVEMENT MATCH TYPE "ML1"	2	EA		
4	THICKENED EDGE PAVEMENT PREP	5,970	LF		
5	REMOVE EXISTING CONCRETE CURB	5,290	LF		
6	REMOVE EXISTING CONCRETE SPILLWAY	11	EA		
7	SHOULDERING MATERIAL	484	TN		
8	SHOULDER BUILD-UP AND GRADING	42,071	LF		
9	EX GUARDRAIL HEIGHT ADJUSTMENT BY RAISING BLOCKS	2,413	LF		
10	GUARDRAIL, W-BEAM, SINGLE FACE, STEEL POSTS W/ 8" MONDO BLOCKS	263	LF		
11	REMOVE & REPLACE DAMAGED WOOD BLOCKS (8")	50	EA		
12	INSTALL NEW TERMINAL END TREATMENT (46'-10.5" MSKT/TL-3)	6	EA		
13	REMOVE EXISTING GUARDRAIL END TREATMENT	488	LT		
14	CREATE NEW GUARDRAIL POST LEAVE-OUT IN EXISTING SPILLWAY	1	EA		
15	PERMANENT PAVEMENT MARKINGS - WHITE (4" EQUIV.) P1 & P2	128,331	LF		
16	PERMANENT PAVEMENT MARKINGS - YELLOW (4" EQUIV.) P1 & P2	76,761	LF		
17	CONSTRUCTION SURVEY AND LAYOUT	1	LS		
18	MOBILIZATION	1	LS		
19	QUALITY CONTROL AND TESTING	1	LS		
20	TRAFFIC CONTROL	1	LS		
21	FORCE ACCOUNT	1	LS	\$ 325,000.00	\$ 325,000.00
TOTAL AMOUNT BID					

TOTAL AMOUNT BID - (numbers and words): \$ _____

BID SCHEDULE

OLD HIGHWAY 66 OVERLAY (FY 25-26) IN YAVAPAI COUNTY, ARIZONA

PROJECT #2450129

FIRM: _____

BY: _____

TITLE: _____

EMAIL: _____